

606 WM Leigh Drive Tullytown PA 19007 215-943-3382

Client: Dawn Ranochak Home: (215) 791-5716

Property: 11 Kraft Lane

Levittown, PA 19055

Operator: TRISTATE

(215) 943-3382 Estimator: Gary Poltonowicz **Business:**

Company: MDL Restoration Inc E-mail: Gary@mdlrestorationinc.com

Business: 606 WM Leigh Drive

Tullytown, PA 19007

Type of Estimate: Water Damage

> Date Entered: 3/29/2021 Date Assigned:

Price List: PAPH8X_MAR21

Labor Efficiency: Restoration/Service/Remodel


> Estimate: RANOCHAK-REBUILD

File Number: A00003212481

606 WM Leigh Drive Tullytown PA 19007 215-943-3382

RANOCHAK-REBUILD

Main Level



Bathroom Height: 8'

> 188.00 SF Walls 221.60 SF Walls & Ceiling 3.73 SY Flooring 23.50 LF Ceil. Perimeter

33.60 SF Ceiling 33.60 SF Floor 23.50 LF Floor Perimeter


DESCRIPTION	QTY	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
Contents - move out then reset - Small room	1.00 EA		0.00	50.87	0.00	10.18	61.05
2. Detach & Reset Interior door - Colonist - slab only	1.00 EA	21.14	0.00	0.00	0.00	4.22	25.36
3. T- molding - for wood flooring	2.50 LF		0.00	7.37	1.00	3.88	23.31
4. R&R Casing - 3 1/4"	16.00 LF		0.60	2.64	1.59	10.68	64.11
5. 1/2" - drywall per LF - up to 2' tall	6.33 LF		0.00	11.95	0.47	15.22	91.33
6. Additional cost for gluing drywall	12.66 SF		0.00	0.34	0.04	0.86	5.20
7. Baseboard - 3 1/4"	6.33 LF		0.00	3.17	0.49	4.12	24.68
8. Pedestal sink - Detach & reset	1.00 EA		0.00	316.84	0.00	63.36	380.20
9. P-trap assembly - Detach & reset	1.00 EA		0.00	66.81	0.00	13.36	80.17
10. Remove Plumbing fixture supply line	3.00 EA		5.89	0.00	0.00	3.54	21.21
11. Install Plumbing fixture supply line	3.00 EA		0.00	15.18	0.00	9.10	54.64
12. Toilet - Reset	1.00 EA		0.00	165.02	0.36	33.08	198.46
13. Baseboard heat - steam/hot wtr cover only - Detach & reset	4.40 EA		0.00	13.41	0.00	11.80	70.80
14. Remove Ceramic/porcelain tile	33.60 SF		2.11	0.00	0.00	14.18	85.08
Removal							
15. Clean floor	33.60 SF		0.00	0.40	0.97	2.68	17.09
16. Material Only Tile - per specs from independent tile analysis	33.60 SF		0.00	0.00	0.00	0.00	0.00
Waiting in ITEL Pricing (Material only)							
17. Install Ceramic/porcelain tile	33.60 SF		0.00	8.57	0.00	57.60	345.55
Install							
18. R&R Mortar bed for tile	33.60 SF		1.71	7.61	3.33	63.30	379.79
19. Tile/stone sealer	33.60 SF		0.00	0.97	0.63	6.64	39.86
20. R&R Quarter round - 3/4"	4.92 LF		0.20	1.56	0.21	1.78	10.65



606 WM Leigh Drive Tullytown PA 19007 215-943-3382

CONTINUED - Bathroom

DESCRIPTION	QTY	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
21. Mask the floor per square foot - plastic and tape - 4 mil	33.60 SF		0.00	0.22	0.10	1.50	8.99
22. Detach & Reset Light fixture	1.00 EA	61.51	0.00	0.00	0.00	12.30	73.81
23. Shower curtain rod - Detach & reset	1.00 EA		0.00	18.32	0.00	3.66	21.98
24. Seal/prime then paint part of the walls twice (3 coats)	125.33 SF		0.00	1.18	1.96	29.98	179.83
25. Seal & paint door or window opening (per side)	1.00 EA		0.00	28.39	0.27	5.74	34.40
26. Seal & paint door slab only (per side)	1.00 EA		0.00	34.12	0.45	6.92	41.49
27. Seal & paint baseboard - two coats	6.33 LF		0.00	1.34	0.04	1.70	10.22
28. Final cleaning - construction - Residential	33.60 SF		0.00	0.25	0.60	1.68	10.68
Totals: Bathroom					12.51	393.06	2,359.94



Hvac Height: 8'

> 68.00 SF Walls 72.43 SF Walls & Ceiling

0.49 SY Flooring

8.50 LF Ceil. Perimeter

4.43 SF Ceiling


4.43 SF Floor

8.50 LF Floor Perimeter

DESCRIPTION	QTY	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
29. HVAC - General Laborer - per hour	1.50 HR		0.00	46.18	0.00	13.86	83.13
Metal fire wall has to be detached and re-	set for drywall wo	rk					
30. 1/2" - drywall per LF - up to 2' tall	2.00 LF		0.00	11.95	0.15	4.82	28.87
31. Additional cost for gluing drywall	4.00 SF		0.00	0.34	0.01	0.28	1.65
32. Final cleaning - construction - Residential	4.43 SF		0.00	0.25	0.08	0.22	1.41
Totals: Hvac					0.24	19.18	115.06



606 WM Leigh Drive Tullytown PA 19007 215-943-3382



Hallway Height: 8'

> 148.90 SF Walls 170.85 SF Walls & Ceiling 2.44 SY Flooring 20.83 LF Ceil. Perimeter

21.95 SF Ceiling 21.95 SF Floor 18.17 LF Floor Perimeter

Missing Wall - Goes to Floor

2' 8" X 6' 8"

Opens into FAMILY_ROOM

DESCRIPTION	QTY	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
33. Contents - move out then reset - Small room	1.00 EA		0.00	50.87	0.00	10.18	61.05
34. Bifold door - (2 slabs only) - Single - Detach & reset	1.00 EA		0.00	16.92	0.00	3.38	20.30
35. R&R T- molding - for wood flooring	2.50 LF		0.45	7.37	1.00	4.10	24.66
36. R&R End molding - for wood flooring	2.50 LF		0.45	6.30	0.84	3.54	21.26
37. Material Only Snaplock Laminate - per specs from independent analysis	21.95 SF		0.00	0.99	0.57	4.46	26.76
.99 a SF as per ITEL Pricing (Material o	nly)						
38. Install Snaplock Laminate - simulated wood flooring	21.95 SF		0.00	2.48	0.00	10.88	65.32
Install							
39. Vapor barrier - visqueen - 6mil	21.95 SF		0.00	0.29	0.07	1.30	7.74
40. R&R Baseboard - 3 1/4"	18.17 LF		0.54	3.17	1.40	13.76	82.57
41. Quarter round - 3/4"	18.17 LF		0.00	1.56	0.77	5.84	34.96
42. Mask the floor per square foot - plastic and tape - 4 mil	21.95 SF		0.00	0.22	0.07	0.98	5.88
43. Seal/prime then paint more than the floor perimeter twice (3 coats)	72.67 SF		0.00	1.18	1.13	17.38	104.26
Under Chair Rail							
44. Seal & paint chair rail - two coats	18.17 LF		0.00	1.30	0.13	4.74	28.49
45. Seal & paint door or window opening (per side)	4.00 EA		0.00	28.39	1.08	22.94	137.58
46. Seal & paint door slab only (per side)	2.00 EA		0.00	34.12	0.91	13.82	82.97
47. Seal & paint bifold door set - slab only (per side)	1.00 EA		0.00	45.46	0.86	9.28	55.60
48. Seal & paint baseboard - two coats	18.17 LF		0.00	1.34	0.12	4.90	29.37
49. Seal & paint base shoe or quarter round	18.17 LF		0.00	0.73	0.11	2.68	16.05
50. Final cleaning - construction - Residential	21.95 SF		0.00	0.25	0.40	1.10	6.99



Family Room

606 WM Leigh Drive Tullytown PA 19007 215-943-3382

CONTINUED - Hallway

DESCRIPTION	QTY	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
Totals: Hallway					9.46	135.26	811.81

Height: 8'


### 10" 15' 1" 15	443.22 SF Walls 698.42 SF Walls & Ceiling 28.36 SY Flooring 65.83 LF Ceil. Perimeter 2' 6" X 8' Ope				255.20 SF Ceiling 255.20 SF Floor 56.42 LF Floor Perimeter				
Missing Wall	2' 6	5'' X 8'		Opens into	Exterior				
Missing Wall - Goes to Floor	2' 8	S'' X 6' 8''		Opens into	HALLWAY	•			
Missing Wall - Goes to Floor	6' 9	'' X 6' 8''		Opens into	KITCHEN				
Window	2' 7'' X 4' Opens into Exterior								
Window	2' 7	''' X 4'		Opens into	Exterior				
DESCRIPTION	QTY	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL		
51. Content Manipulation charge - per hour	6.00 HR		0.00	46.18	0.00	55.42	332.50		
52. Provide box, packing paper & tape - medium size	5.00 EA		0.00	3.90	2.49	4.10	26.09		
53. Detach & Reset Interior door - Colonist - slab only	1.00 EA	21.14	0.00	0.00	0.00	4.22	25.36		
54. Baseboard heat - steam/hot wtr cover only - Detach & reset	16.00 EA		0.00	13.41	0.00	42.92	257.48		
55. R&R T- molding - for wood flooring	6.75 LF		0.45	7.37	2.71	11.10	66.60		
56. R&R End molding - for wood flooring	3.00 LF		0.45	6.30	1.01	4.26	25.52		
57. Remove Snaplock Laminate - simulated wood flooring	249.20 SF		1.38	0.00	0.00	68.78	412.68		
Removal									
58. Remove Vapor barrier - visqueen - 6mil	249.20 SF		0.09	0.00	0.00	4.48	26.91		
59. Material Only Snaplock Laminate - per specs from independent analysis	255.20 SF		0.00	0.99	6.58	51.86	311.09		
.99 a SF as per ITEL Pricing (Material o	nly)								
60. Install Snaplock Laminate - simulated wood flooring	255.20 SF		0.00	2.48	0.00	126.58	759.48		
Install									
61. Vapor barrier - visqueen - 6mil	255.20 SF		0.00	0.29	0.77	14.96	89.74		
62. Remove Quarter round - 3/4"	48.42 LF		0.20	0.00	0.00	1.94	11.62		
ANOCHAK-REBUILD					4/1	/2021	Page: 5		



606 WM Leigh Drive Tullytown PA 19007 215-943-3382

CONTINUED - Family Room

DESCRIPTION	QTY	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
63. Quarter round - 3/4"	56.42 LF		0.00	1.56	2.40	18.08	108.50
64. Mask the floor per square foot - plastic and tape - 4 mil	255.20 SF		0.00	0.22	0.77	11.38	68.29
65. Window blind - horizontal or vertical - Detach & reset	2.00 EA		0.00	39.23	0.00	15.70	94.16
66. Seal/prime then paint more than the floor perimeter twice (3 coats)	225.67 SF		0.00	1.18	3.52	53.96	323.77
Under Chair Rail							
67. Seal & paint chair rail - two coats	56.42 LF		0.00	1.30	0.41	14.76	88.52
68. Seal & paint crown molding - two coats	65.83 LF		0.00	1.36	0.51	18.00	108.04
69. Seal & paint door or window opening (per side)	5.00 EA		0.00	28.39	1.34	28.66	171.95
70. Seal & paint baseboard - two coats	56.42 LF		0.00	1.34	0.37	15.20	91.17
71. Seal & paint base shoe or quarter round	56.42 LF		0.00	0.73	0.34	8.30	49.83
72. Final cleaning - construction - Residential	255.20 SF		0.00	0.25	4.60	12.76	81.16
Totals: Family Room					27.82	587.42	3,530.46



Height: 8' Kitchen

> 285.56 SF Walls 497.60 SF Walls & Ceiling 19.60 SY Flooring 64.67 LF Ceil. Perimeter

212.04 SF Ceiling 176.43 SF Floor 33.91 LF Floor Perimeter

Missing Wall - Goes to Floor	4' 2" X 6' 8"	Opens into Exterior
Window	2' 7" X 2' 3"	Opens into Exterior
Missing Wall	3' 4" X 8'	Opens into Exterior
Missing Wall - Goes to Floor	6' 9" X 6' 8"	Opens into FAMILY_ROOM

DESCRIPTION	QTY	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
73. Content Manipulation charge - per hour	12.00 HR		0.00	46.18	0.00	110.84	665.00
74. Provide dishpack box, packing paper & tape	5.00 EA		0.00	7.70	5.25	8.16	51.91
75. Provide box, packing paper & tape - small size	6.00 EA		0.00	2.45	2.00	3.12	19.82
76. Provide box, packing paper & tape - medium size	5.00 EA		0.00	3.90	2.49	4.10	26.09



CONTINUED - Kitchen

DESCRIPTION	QTY	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
77. Bubble Wrap - Add-on cost for fragile items	60.00 LF		0.00	0.22	1.80	2.80	17.80
78. Detach & Reset Refrigerator - bottom freezer - 25 to 30 cf	1.00 EA	49.54	0.00	0.00	0.00	9.90	59.44
79. Detach & Reset Range - freestanding - electric	1.00 EA	37.16	0.00	0.00	0.00	7.44	44.60
80. Microwave oven - over range type - Detach & reset	1.00 EA		0.00	143.81	0.00	28.76	172.57
81. Dishwasher - Detach & reset	1.00 EA		0.00	261.26	0.00	52.26	313.52
82. R&R Glass tile - High grade	65.21 SF		2.11	33.35	93.78	481.24	2,887.36
83. Add-on for tile backsplash installation	65.21 SF		0.00	15.98	0.00	208.42	1,250.48
84. Seal grout on tile wall	65.21 SF		0.00	1.56	0.63	20.46	122.82
85. Detach & Reset Sink faucet - Kitchen	1.00 EA	134.05	0.00	0.00	0.00	26.82	160.87
86. Garbage disposer - Detach & reset	1.00 EA		0.00	179.09	0.00	35.82	214.91
87. P-trap assembly - Detach & reset	1.00 EA		0.00	66.81	0.00	13.36	80.17
88. Remove Plumbing fixture supply line	2.00 EA		5.89	0.00	0.00	2.36	14.14
89. Install Plumbing fixture supply line	2.00 EA		0.00	15.18	0.00	6.08	36.44
90. Sink - undermount - Detach & reset	1.00 EA		0.00	277.37	0.08	55.50	332.95
91. Countertop - solid surface/granite - Detach & reset	40.10 SF		0.00	32.11	0.00	257.52	1,545.13
Attempt to detach an reset will be made, or replacement.	due to natural sto	ne it might cro	ack at the weak	point (Sink&fau	cet). If so a sup	plement will b	e made for
92. R&R Cabinetry - lower (base) units - High grade	13.00 LF		8.83	242.88	159.75	686.40	4,118.38
93. Toe kick - pre-finished wood - 1/2"	13.00 LF		0.00	9.19	3.32	24.56	147.35
94. R&R Cabinetry - full height unit - High grade	2.33 LF		10.60	328.56	39.20	165.88	995.32
95. R&R Cabinetry - upper (wall) units - High grade	21.58 LF		8.83	178.67	182.05	845.68	5,073.98
96. Add for leaded glass (standard design), per cabinet door	2.00 EA		0.00	64.86	7.78	27.50	165.00
97. R&R Cabinet knob or pull	20.00 EA		1.37	8.38	4.25	39.86	239.11
98. R&R Cabinet panels - side, end, or back	74.25 SF		2.28	15.55	34.21	271.62	1,629.71
99. R&R Cabinet door - High grade	2.00 SF		3.53	27.32	2.82	12.90	77.42
False doors							
100. R&R Quarter round - 3/4" - stain grade	43.16 LF		0.20	1.89	2.69	18.58	111.47
ANOCHAK-REBUILD					4/	1/2021	Page:
							J



CONTINUED - Kitchen

DESCRIPTION	QTY	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
Upper cab crown trim							
101. R&R Stair nosing - for wood flooring	4.17 LF		0.45	9.31	2.12	8.56	51.38
102. R&R Casing - 3 1/4"	48.00 LF		0.60	2.64	4.78	32.06	192.36
103. R&R Baseboard - 3 1/4"	6.33 LF		0.54	3.17	0.49	4.80	28.78
104. 1/2" - drywall per LF - up to 4' tall	3.00 LF		0.00	16.98	0.41	10.26	61.61
105. Additional cost for gluing drywall	12.00 SF		0.00	0.34	0.04	0.82	4.94
106. Baseboard heat - steam/hot wtr cover only - Detach & reset	10.00 EA		0.00	13.41	0.00	26.82	160.92
107. Remove Ceramic/porcelain tile	172.43 SF		2.11	0.00	0.00	72.76	436.59
Removal							
108. Clean floor	88.21 SF		0.00	0.40	2.54	7.06	44.88
109. Material Only Tile - per specs from independent tile analysis	176.43 SF		0.00	0.00	0.00	0.00	0.00
Waiting in ITEL Pricing (Material only))						
110. Install Ceramic/porcelain tile	176.43 SF		0.00	8.57	0.00	302.40	1,814.41
Install							
111. R&R Mortar bed for tile	176.43 SF		1.71	7.61	17.47	332.36	1,994.16
112. Tile/stone sealer	176.43 SF		0.00	0.97	3.28	34.88	209.30
113. Mask the floor per square foot - plastic and tape - 4 mil	176.43 SF		0.00	0.22	0.53	7.86	47.20
114. Window blind - horizontal or vertical - Detach & reset	1.00 EA		0.00	39.23	0.00	7.84	47.07
115. Ceiling fan - Detach & reset	1.00 EA		0.00	219.06	0.00	43.82	262.88
116. Recessed light fixture - Detach & reset trim only	4.00 EA		0.00	3.57	0.00	2.86	17.14
117. Seal/prime then paint the walls and ceiling twice (3 coats)	497.60 SF		0.00	1.18	7.76	119.00	713.93
118. Seal & paint door or window opening (per side)	4.00 EA		0.00	28.39	1.08	22.94	137.58
119. Seal & paint baseboard - two coats	33.91 LF		0.00	1.34	0.22	9.12	54.78
120. Final cleaning - construction - Residential	461.99 SF		0.00	0.25	8.32	23.10	146.92
Totals: Kitchen					591.14	4,497.26	27,000.59
Total: Main Level					641.17	5,632.18	33,817.86



General

DESCRIPTION	QTY	RESET	REMOVE	REPLACE	TAX	O&P	TOTAL
121. Single axle dump truck - per load - including dump fees	1.00 EA		366.56	0.00	0.00	73.32	439.88
122. Taxes, insurance, permits & fees (Bid Item)	1.00 EA		0.00	0.00	0.00	0.00	0.00
If permits are needed will bill as incurred	d.						
123. Lead Paint Safety (Bid Item)	1.00 EA		0.00	0.00	0.00	0.00	0.00
124. Floor protection - cloth - skid resistant, leak proof	200.00 SF		0.95	0.00	4.20	38.84	233.04
125. Personal protective mask (N-95)	16.00 EA		0.00	4.10	8.94	13.90	88.44
Totals: General					13.14	126.06	761.36
Line Item Totals: RANOCHAK-REBU	ILD				654.31	5,758.24	34,579.22

Grand Total Areas:

491.61	SF Walls SF Floor SF Long Wall	54.62	SF Ceiling SY Flooring SF Short Wall	140.49	SF Walls and Ceiling LF Floor Perimeter LF Ceil. Perimeter
.,	Floor Area Exterior Wall Area		Total Area Exterior Perimeter of Walls	1,160.34	Interior Wall Area
	Surface Area Total Ridge Length		Number of Squares Total Hip Length	0.00	Total Perimeter Length



Summary

Line Item Total	28,166.67
Material Sales Tax	613.83
Cleaning Mtl Tax	9.94
Subtotal	28,790.44
Overhead	2,879.12
Profit	2,879.12
Cleaning Sales Tax	30.54
Replacement Cost Value	\$34,579.22
Net Claim	\$34,579.22

Gary Poltonowicz

RANOCHAK-REBUILD Page: 10 4/1/2021





Recap of Taxes, Overhead and Profit

Overhead (10%)	Profit (10%)	Material Sales Tax (6%)	Cleaning Mtl Tax (6%)	Cleaning Sales Tax (6%)	Clothing Acc Tax (6%)	Manuf. Home Tax (6%)	0	Dryclean/Laun dry Tax (6%)
Line Items								
2,879.12	2,879.12	613.83	9.94	30.54	0.00	0.00	0.00	0.00
Total								
2,879.12	2,879.12	613.83	9.94	30.54	0.00	0.00	0.00	0.00



Recap by Room

Estimate: RANOCHAK-REBUILD

Area: Main Level		
Bathroom	1,954.37	6.94%
Hvac	95.64	0.34%
Hallway	667.09	2.37%
Family Room	2,915.22	10.35%
Kitchen	21,912.19	77.79%
Area Subtotal: Main Level	27,544.51	97.79%
General	622.16	2.21%
Subtotal of Areas	28,166.67	100.00%
Total	28,166.67	100.00%






Recap by Category

O&P Items	Total	%
APPLIANCES	670.86	1.94%
CABINETRY	10,692.31	30.92%
CLEANING	243.02	0.70%
CONTENT MANIPULATION	932.98	2.70%
CONT: PACKING,HANDLNG,STORAGE	105.40	0.30%
GENERAL DEMOLITION	2,497.06	7.22%
DOORS	59.20	0.17%
DRYWALL	160.22	0.46%
FLOOR COVERING - WOOD	1,202.18	3.48%
FINISH CARPENTRY / TRIMWORK	472.32	1.37%
FINISH HARDWARE	18.32	0.05%
HAZARDOUS MATERIAL REMEDIATION	65.60	0.19%
HEAT, VENT & AIR CONDITIONING	476.93	1.38%
LIGHT FIXTURES	294.85	0.85%
PLUMBING	1,102.80	3.19%
PAINTING	2,134.37	6.17%
TILE	6,920.56	20.01%
WINDOW TREATMENT	117.69	0.34%
O&P Items Subtotal	28,166.67	81.46%
Material Sales Tax	613.83	1.78%
Cleaning Mtl Tax	9.94	0.03%
Overhead	2,879.12	8.33%
Profit	2,879.12	8.33%
Cleaning Sales Tax	30.54	0.09%
Total	34,579.22	100.00%

RANOCHAK-REBUILD Page: 13 4/1/2021





Main Level